



Specialists in movable walls and sliding folding partitions

SOLUTIONS

CE SOLUTIONS - RISK ASSESSMENT

CE Solutions Ltd
The Old Eltex Works, Watery Lane
Worcester. WR2 5AR
Phone: 01905 422533
Fax: 01905 422538
www.resolutions.co.uk

MANUAL HANDLING

Task on Which Assessment is made	Unloading Panels & Materials. Hauling to Work Site. Lifting into Position.
Hazard Identified	Muscular-Skeletal Disorders. Strains & Sprains. Damage to Hands & Feet
Persons Considered to be at Risk	Operatives
Assessment Made	Medium Risk
Training Undertaken	Operatives are familiar with Kinetic Handling Technics & Team Lifting
Who will Implement Action Required	Installation Manager. Controlling Lift.
Control Measures Required	Mechanical lifting equipment to be used whenever possible. Operatives will be selected for physical attributes and general health in accordance with the demands of the work. Only experienced and competent operatives used. Work area cleared and kept clear and unobstructed at all times. A safe & clear access must be ascertained before offloading. Use of gloves and safety footwear. If mechanical lifting equipment is neither available nor practical then sufficient labour will be supplied.

MOBILE TOWER

Task on Which Assessment is made	Working from stepladder
Hazard Identified	Falls of persons / materials
Persons Considered to be at Risk	Operative & Others Passing By Stepladder
Assessment Made	Low risk
Training Undertaken	Tool box talks. Site induction
Who will Implement Action Required	Operatives
Control Measures Required	Tower erected by site Installation Manager certified in mobile tower erection. Double guardrails and toe boards will be fitted in accordance with 1996 Health & Safety Construction Regulations. Signage on tower (Men Working Overhead) possible exclusion zone to be erected. Tower to be inspected weekly by Installation Manager. All scaffold/tower erectors are PASMA qualified.

VAT No. 865 1410 34
Reg. in England no: 5600568

Registered office:
Westview House
Neweys Hill
Worcester

S a l e s • S e r v i c e • R e p a i r



RISK ASSESSMENT CONTINUED:

Project:

Contractor:

Tasks:

USE OF POWER TOOLS

Task on Which Assessment is made	Drilling into concrete. Cutting aluminium/MFC profile.
Hazard Identified	Serious injury. Electric shocks. Eye Injuries
Persons Considered to be at Risk	Operatives Primary
Assessment Made	Medium Risk
Training Undertaken	Tool Box Talks
Who will Implement Action Required	Operatives
Control Measures Required	Tools inspected and PAT tested. Tools to be 110V/Battery Operated. All leads to be checked for cuts etc. Cut off saw to be fully guarded as manufacturer's specification. PPE : Goggles, Hard Hat, Protective Footwear.

STEP LADDERS

Task on Which Assessment is made	Working from Step Ladder
Hazard Identified	Falls of Persons/Materials
Persons Considered to be at Risk	Operatives & Others Passing By Stepladder
Assessment Made	Low Risk
Training Undertaken	Tool Box Talks. Site Induction
Who will Implement Action Required	Operatives
Control Measures Required	Stepladders may only be used in areas where it is not practical to use mobile platforms or heights less than 3 metres and must be on a firm level base. Stepladders to be individually inspected before they are used. All stepladders to be Class 1 Industrial Grade. Persons using the stepladder must not work any higher than three steps down from the top. Work area must be above the ladder, ie must be within easy reach, without leaning out away from ladder.